

Mechatronics Technician Commissioning Protocol GUIDE Part 1 and 2



German American
Chambers of Commerce
Deutsch-Amerikanische
Handelskammern

**German American Chamber of Commerce
of the Midwest, Inc.**

150 North Michigan Avenue, 35th Floor
Chicago, Illinois 60601

Phone: +1 (312) 644-2662 | Fax: +1 (312) 644-0738
www.gaccmidwest.org

AHK USA-Chicago	First and last name:	Commissioning booklet
Final Examination Part 1 and Part 2		
Checks - Commissioning Protocols	Mechatronics Technician	

IMPORTANT INFORMATION!

READ all information provided CAREFULLY

During the Part 1 examination you will complete the following commissioning protocol. Once everything is ready and all modification have been made, you will request an exam board member observe your commissioning protocol. You will take them through every single point on this document. The highlighted BLUE instructions shown in this guide are provided to ensure that you know what is expected of you when you take your exam board member through the Commissioning protocol. **KEY POINTS:** Explain and talk through everything that you are checking. Do not just mention things, actually demonstrate what you are checking to prove that all is ok. Do not skip any steps. Be prepared to independently (without assistance or questions from the exam board) walk through every step.

During the Part 2 examination you will also be expected to independently commission your mechatronics system, doing similar thorough checks of mechanical, pneumatic and electric systems, as well as take appropriate voltage measurements. However, you will not have the commissioning protocol provided. You may prepare your own (highly recommended) in your preparation binder for exam day, but no exam protocol will be provided to you on the day of the exam. To properly prepare for your exam, you should use this Practice Guide prior to the examination to make sure that you are capable of going through each step and taking accurate measurements. You will have to demonstrate this on exam day when you turn your exam project in to your customer (the exam board)!

On exam day you should plan for 1.5-2.5 hours to complete this commissioning with an exam board member present. This time is included in your 6.5 total hours.

AHK USA-Chicago	First and last name:	Commissioning booklet
Final Examination Part 1 and Part 2		
Checks - Commissioning Protocols	Mechatronics Technician	

The mechatronic subsystem is to be checked and put into operation in accordance with the commissioning protocol. The following commissioning protocol is to be completed with an exam board member observing. You will walk the exam board member through each step of inspection and measurement checks. Demonstrate to the exam board member that everything is in proper working order. Do not skip any steps or check points. If you come across any issues or problems they are to be fixed independently either before moving to the next checking point on the list or returning to fix them once the entire commissioning is complete and time remains. **Attention! ALL work steps must be carried out under the supervision of the testing committee!**

Steps 1 to 3 should be carried out in a de-energized and de-pressurized state.

Step 1: Inspection of the mechanical system – assembly grid

Perform a visual inspection and decide for each inspection item whether or not there are any defects. Demonstrate your checks, explain what you are checking and document your results. Do not skip any checking points!

Check no.	Inspection item	OK	
1	Drawings available and complete	yes <input type="checkbox"/>	no <input type="checkbox"/>
2	Assembled according to general chute drawing	yes <input type="checkbox"/>	no <input type="checkbox"/>
3	All components securely fastened	yes <input type="checkbox"/>	no <input type="checkbox"/>
4	No damage to components	yes <input type="checkbox"/>	no <input type="checkbox"/>
5	Components deburred	yes <input type="checkbox"/>	no <input type="checkbox"/>
6	Cylinder runs smoothly	yes <input type="checkbox"/>	no <input type="checkbox"/>



1. Physically check and show exam board member that all pages are available.
2. Verbally explain what is assembled on the grid, where things are, any changes you have made, show and refer to the available mechanical drawings.
3. Actually wiggle multiple mechanical components on the assembly grid, checking screws etc. to demonstrate they are securely fastened.
4. Visually look for damage or corrosion. If any exists, point out and explain.
5. Use your fingernail to check pieces for sharp edges, explain what you are looking for and if you find anything.
6. Actually unhook all air hoses from the cylinders, demonstrate that they operate smoothly as a mechanical component.

If anything is a “no” mark it “no” to go back to later or fix immediately if it can be done with little delay.



Step 2: Inspection of the pneumatic system

Perform a visual inspection and decide for each inspection item whether or not there are any defects. Demonstrate your checks, explain what you are checking and document your results. Do not skip any checking points!

Check no.	Inspection item	OK	
1	Assembled according to installation drawing and labeled	yes <input type="checkbox"/>	no <input type="checkbox"/>
2	All pneumatic lines securely fastened	yes <input type="checkbox"/>	no <input type="checkbox"/>
3	Pneumatic lines properly routed	yes <input type="checkbox"/>	no <input type="checkbox"/>
4	No damage to components	yes <input type="checkbox"/>	no <input type="checkbox"/>



1. Refer to drawing, point out the items on the assembly grid and that they are properly labeled.
2. Actually pull on all pneumatics lines firmly, demonstrating they are secure.
3. Point out proper routing of air lines and check for pinched lines.
4. Physically check and inspect all lines for cracks or other damage.

If anything is a “no” mark it “no” to go back to later or fix immediately if it can be done with little delay.

Step 3: Inspection of the electrical engineering

Perform a visual inspection and decide for each inspection item whether or not there are any defects. Demonstrate your checks, explain what you are checking and document your results. Do not skip any checking points!

Check no.	Inspection item	OK	
1	Circuit diagrams available and complete	yes <input type="checkbox"/>	no <input type="checkbox"/>
2	Proper installation of operating equipment	yes <input type="checkbox"/>	no <input type="checkbox"/>
3	Ground wire properly connected	yes <input type="checkbox"/>	no <input type="checkbox"/>
4	Terminal securely fastened	yes <input type="checkbox"/>	no <input type="checkbox"/>
5	No damaged wiring	yes <input type="checkbox"/>	no <input type="checkbox"/>
6	Wiring in accordance with wiring diagrams	yes <input type="checkbox"/>	no <input type="checkbox"/>
7	No damage to operating equipment	yes <input type="checkbox"/>	no <input type="checkbox"/>



1. Physically check, count and show pages of schematic diagrams available to supervising exam board member.
2. Physically shake, move, all electrical components in the cabinet, on the assembly grid and control box
3. Check all earth ground connections with a DMM and by hand, explain your checks
4. Remove all covers and look for loose or exposed wires – spot checking and pulling on some wires from the terminal box
5. Check for loose or exposed wires in wire ways and on the assembly grid
6. Trace 1 wire loop from source to component, then back to incoming power source
7. Visually check, pointing to inspected areas looking for cracks, burns, broken parts

If anything is a “no” mark it “no” to go back to later or fix immediately if it can be done with little delay. Be sure you are talking the exam board through each step that you are taking.

Continuity and low impedance of the protective earth wire are present: yes no

Attention: Electronic components must be disconnected prior to the isolation measurement. With the protected extra-low voltage (PELV), the jumper to the ground wire must be removed before any isolation measurements are taken.

Check no.	Measurement	Measurement location	Measured value	Standard value
2a	Isolation resistance 208V	-X2: L1 to PE -X2: L2 to PE -X2: L3 to PE -X2: N to PE -X2: L1 to L2 -X2: L1 to L3 -X2: L2 to L3 -X3: 1 to PE -X3: 3 to PE -X3: 5 to PE		
3a	Isolation resistance 24 V DC	L1 to +24 V L2 to +24 V L3 to +24 V N to +24V		

List specification used: _____

Measured values meet specifications: yes no

1-4 Know where each checking point is and talk the exam board through your measurement process.

Unplug power to the power supply and PELV to X1

Make sure you know what the specifications/standard values are for your equipment, so that you can explain if the specifications are met in 1-3. You may bring a specification sheet specific to your equipment or devices used.

Ensure that your prob tips are actually in contact when making measurements. If your probs need to be longer, bring longer ones for the exam.

Step 5: Voltage and rotary field measurement

Prior to the start-up of the mechatronic part system, perform and document the required measurements. Demonstrate your checks, explain what you are checking and document your results. Do not skip any checking points!

Note: First check that all overload protection elements are switched off!

Check no.	Measurement/activity	Measurement locations	Measured value
1	Supply voltage (main switch -Q1 "ON")		
2	Control voltage 24 V (circuit breaker -F3 "ON")		
3	Control voltage 24 V (circuit breaker -F4 "ON")		
4	Rotary field – X13 (clockwise rotation)		yes <input type="checkbox"/> no <input type="checkbox"/>

Step 6: GFCI and Emergency off test

Test whether the GFCI is activated using the test button.

GFCI activated: yes no

Test your emergency – stop function.

Emergency switches off: yes no

(Explain testing procedure, test lights, e-stop and safety circuits)

Discuss your further procedure with the testing committee!

Be sure you know where your checking points are! Explain your steps to the exam board as you check.

Step 8: Testing by hand

Perform a test by hand and decide for each inspection item whether or not there are any defects. Demonstrate your checks, explain what you are checking and document your results. Do not skip any checking points!

Attention! Follow health and safety regulations and put on your safety goggles.

Check no.	Inspection item	OK	
1	Setting the operating pressure to 5 bar and doing a leak test	yes <input type="checkbox"/>	no <input type="checkbox"/>
2	Cylinder can be controlled manually via the manual auxiliary actuator	yes <input type="checkbox"/>	no <input type="checkbox"/>
3	Setting the throttle check valves to a slow, safe cylinder activation	yes <input type="checkbox"/>	no <input type="checkbox"/>
4	Proximity switches are adapted to the travel of the cylinder and the corresponding inputs on the control system	Yes <input type="checkbox"/>	no <input type="checkbox"/>
5	Testing and adjusting other sensors and the corresponding inputs at the control system	yes <input type="checkbox"/>	no <input type="checkbox"/>



1. Verify and adjust incoming air pressure and manually test for leaks listening for air
2. Move cylinders manually using the test buttons on the valves
3. Set the speed of each cylinder and move manually to demonstrate slow and safe travel
4. Identify and distinguish between proxy cylinder inputs vs inputs to the PLC.
5. Demonstrate sensors are connected and function properly

Step 9: Functional check of the entire system

Perform a functional test and decide for each inspection item, based on the functional description, whether or not there are any defects. Demonstrate your checks, explain what you are checking by reading each function and document your results. Do not skip any checking points! Before submitting final documentation to the the exam board, remaining time may be used to get any function working and change your inspection item from no to yes – a change must be demonstrated to the exam board.

Check no.	Inspection item	OK	
		yes <input type="checkbox"/>	no <input type="checkbox"/>
1	Description according to functional description no. I	yes <input type="checkbox"/>	no <input type="checkbox"/>
2	Description according to functional description no. II	yes <input type="checkbox"/>	no <input type="checkbox"/>
3	Description according to functional description no. III	yes <input type="checkbox"/>	no <input type="checkbox"/>
4	Description according to functional description no. IV	yes <input type="checkbox"/>	no <input type="checkbox"/>
5	Description according to functional description no. V	yes <input type="checkbox"/>	no <input type="checkbox"/>
6	Description according to functional description no. VI	yes <input type="checkbox"/>	no <input type="checkbox"/>
7	Description according to functional description no. VII	yes <input type="checkbox"/>	no <input type="checkbox"/>
8	Description according to functional description no. VIII	yes <input type="checkbox"/>	no <input type="checkbox"/>



1-8. Read through the functions and show each step! Check every single lamp. Properly select Yes or No according to how the system functions when you are reviewing it with your exam board. Make appropriate notes.

After the functional check, should any time be remaining, you may attempt to correct functional errors and change no to yes. If you are successful, this change should be demonstrated to the exam board.

Hand-off

Submit the documents to the customer (represented by the exam board). Sign below and Hand-off of the work task and the documentation

Apprentice signature _____

Date/time: _____

Received by: _____ (Examiner signature)